

Practitioner's Docket No. 915-007.085

PATENT

IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

In re application of: J. RASANEN et al. Group No.: To Be Assigned
Application No.: 0 To / Be Assigned
Filed: Herewith Examiner: To Be Assigned
For: Protocol Parameter Re-negotiation After Certain Types of
Non-transparent Data Call Handovers

Assistant Commissioner for Patents
Washington, D.C. 20231

TRANSMITTAL OF CERTIFIED COPY

Attached please find the certified copy of the foreign application from which priority is claimed for this case:

Country: International/WIPO
Application Number: PCT/IB03/01443
Filing Date: April 17, 2003

WARNING: "When a document that is required by statute to be certified must be filed, a copy, including a photocopy or facsimile transmission of the certification is not acceptable." 37 C.F.R. § 1.4(f) (emphasis added).


SIGNATURE OF PRACTITIONER

Reg. No. 27,550

Alfred A. Fressola

(type or print name of practitioner)

Tel. No. (203) 261-1234

Ware, Fressola, Van Der Sluys & Adolphson LLP

P.O. Address Bradford Green, Building Five
755 Main Street, P.O. Box 224
Monroe, CT 06468

Customer No.: 004955

NOTE: The claim to priority need be in no special form and may be made by the attorney or agent, if the foreign application is referred to in the oath or declaration, as required by § 1.63.

CERTIFICATE OF MAILING (37 C.F.R. § 1.8a)

I hereby certify that this correspondence is, on the date shown below is being deposited with the United States Postal Service with sufficient postage as first class mail in an envelope addressed to the Assistant Commissioner for Patents, Washington, D.C. 20231. Express

Express Mail No. EV 435648627 US

Date: April 16, 2004


Signature

Annemarie Maher

(type or print name of person certifying)

(Transmittal of Certified Copy [5-4])



**WORLD INTELLECTUAL PROPERTY ORGANIZATION
ORGANISATION MONDIALE DE LA PROPRIÉTÉ INTELLECTUELLE**

34, chemin des Colombettes, Case postale 18, CH-1211 Genève 20 (Suisse)
Téléphone: (41 22) 338 91 11 - e-mail: wipo.mail @ wipo.int. - Fac-similé: (41 22) 733 54 28

**PATENT COOPERATION TREATY (PCT)
TRAITÉ DE COOPÉRATION EN MATIÈRE DE BREVETS (PCT)**

**CERTIFIED COPY OF THE INTERNATIONAL APPLICATION AS FILED
AND OF ANY CORRECTIONS THERETO**

**COPIE CERTIFIÉE CONFORME DE LA DEMANDE INTERNATIONALE, TELLE QU'ELLE
A ÉTÉ DÉPOSÉE, AINSI QUE DE TOUTES CORRECTIONS Y RELATIVES**

International Application No. } PCT/IB 0 3 / 0 1 4 4 3
Demande internationale n° }


International Filing Date } 17 APRIL 2003
Date du dépôt international } (17. 04. 03)

Geneva/Genève, 23 MARCH 2004

(23. 03. 04)

**International Bureau of the
World Intellectual Property Organization (WIPO)**

**Bureau International de l'Organisation Mondiale
de la Propriété Intellectuelle (OMPI)**



J.-L. Baron

Head, PCT Receiving Office Section
Chef de la section "office récepteur du PCT"

lorab

Per Telefax

1/4

PCT REQUEST

030233WO

Original (for SUBMISSION) - printed on 17.04.2003 11:14:18 AM

0	For receiving Office use only	
0-1	International Application No.	PCT / IB 0 3 / 0 1 4 4 3
0-2	International Filing Date	17 APRIL 2003 17.04.03
0-3	Name of receiving Office and "PCT International Application"	INTERNATIONAL BUREAU OF WIPO PCT International Application
0-4	Form - PCT/RO/101 PCT Request	
0-4-1	Prepared using	PCT-EASY Version 2.92 (updated 01.06.2002)
0-5	Petition The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty	
0-6	Receiving Office (specified by the applicant)	International Bureau of the World Intellectual Property Organization (RO/IB)
0-7	Applicant's or agent's file reference	030233WO
I	Title of invention	PROTOCOL PARAMETER RE-NEGOTIATION AFTER CERTAIN TYPES OF NON-TRANSPARENT DATA CALL HANDOVERS
II	Applicant	
II-1	This person is:	applicant only
II-2	Applicant for	all designated States except US
II-4	Name	NOKIA CORPORATION
II-5	Address:	Keilalahdentie 4 FIN-02150 Espoo Finland
II-6	State of nationality	FI
II-7	State of residence	FI
II-11	Applicant's registration No. with the Office	GPA 02/0311
III-1	Applicant and/or inventor	
III-1-1	This person is:	applicant and inventor
III-1-2	Applicant for	US only
III-1-4	Name (LAST, First)	RÄSÄNEN, Juha
III-1-5	Address:	Sinirinnantie 21 FIN-02660 Espoo Finland
III-1-8	State of nationality	FI
III-1-7	State of residence	FI

2/4

PCT/IB03/01443
030233WO

PCT REQUEST

Original (for SUBMISSION) - printed on 17.04.2003 11:14:18 AM

III-2	Applicant and/or inventor	
III-2-1	This person is:	applicant and inventor
III-2-2	Applicant for	US only
III-2-4	Name (LAST, First)	ALA-VANNESLUOMA, Jukka
III-2-5	Address:	Insinöörinkatu 52 A 4 FIN-33720 Tampere Finland
III-2-6	State of nationality	FI
III-2-7	State of residence	FI
IV-1	Agent or common representative; or address for correspondence The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as:	agent
IV-1-1	Name	COHAUSZ & FLORACK (24)
IV-1-2	Address:	Kanzlerstr. 8a D-40472 Düsseldorf Germany
IV-1-3	Telephone No.	+49-211-904900
IV-1-4	Facsimile No.	+49-211-9049049
IV-1-5	e-mail	mail@cohausz-florack.de
V	Designation of States	
V-1	Regional Patent (other kinds of protection or treatment, if any, are specified between parentheses after the designation(s) concerned)	AP: GH GM KE LS MW MZ SD SL SZ TZ UG ZM ZW and any other State which is a Contracting State of the Harare Protocol and of the PCT EA: AM AZ BY KG KZ MD RU TJ TM and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT EP: AT BE BG CH&LI CY CZ DE DK EE ES FI FR GB GR IE IT LU MC NL PT SE SK TR and any other State which is a Contracting State of the European Patent Convention and of the PCT OA: BF BJ CF CG CI CM GA GN GQ GW ML MR NE SN TD TG and any other State which is a member State of OAPI and a Contracting State of the PCT
V-2	National Patent (other kinds of protection or treatment, if any, are specified between parentheses after the designation(s) concerned)	AE AG AL AM AT AU AZ BA BB BG BR BY BZ CA CH&LI CN CO CR CU CZ DE DK DM DZ EC EE ES FI GB GD GE GH GM HR HU ID IL IN IS JP KE KG KP KR KZ LC LK LR LS LT LU LV MA MD MG MK MN MW MX MZ NO NZ OM PH PL PT RO RU SD SE SG SI SK SL TJ TM TN TR TT TZ UA UG US UZ VC VN YU ZA ZM ZW

3/4

030233WO

PCT REQUEST

Original (for SUBMISSION) - printed on 17.04.2003 11:14:18 AM


V-5	Precautionary Designation Statement In addition to the designations made under items V-1, V-2 and V-3, the applicant also makes under Rule 4.9(b) all designations which would be permitted under the PCT except any designation(s) of the State(s) indicated under item V-6 below. The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit.		
V-6	Exclusion(s) from precautionary designations	NONE	
VI	Priority claim	NONE	
VII-1	International Searching Authority Chosen	European Patent Office (EPO) (ISA/EP)	
VIII	Declarations	Number of declarations	
VIII-1	Declaration as to the identity of the inventor	-	
VIII-2	Declaration as to the applicant's entitlement, as at the international filing date, to apply for and be granted a patent	-	
VIII-3	Declaration as to the applicant's entitlement, as at the international filing date, to claim the priority of the earlier application	-	
VIII-4	Declaration of inventorship (only for the purposes of the designation of the United States of America)	-	
VIII-5	Declaration as to non-prejudicial disclosures or exceptions to lack of novelty	-	
IX	Check list	number of sheets	electronic file(s) attached
IX-1	Request (including declaration sheets)	4	-
IX-2	Description	25	-
IX-3	Claims	11	-
IX-4	Abstract	1	EZABST00.TXT
IX-5	Drawings	5	-
IX-7	TOTAL	46	
	Accompanying items	paper document(s) attached	electronic file(s) attached
IX-8	Fee calculation sheet	✓	-
IX-17	PCT-EASY diskette	-	Diskette
IX-19	Figure of the drawings which should accompany the abstract	2	
IX-20	Language of filing of the international application	English	

4/4

030233WO

PCT REQUEST

Original (for SUBMISSION) - printed on 17.04.2003 11:14:18 AM

X-1	Signature of applicant, agent or common representative	
X-1-1	Name	COHAUSZ & FLORACK (24)
X-1-2	Name of signatory	R. Knauf
X-1-3	Capacity	Patent Attorney

FOR RECEIVING OFFICE USE ONLY

10-1	Date of actual receipt of the purported international application	17 APRIL 2003	17. 04. 03
10-2	Drawings:		
10-2-1	Received		
10-2-2	Not received		
10-3	Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application		
10-4	Date of timely receipt of the required corrections under PCT Article 11(2)		
10-5	International Searching Authority	ISA/EP	
10-6	Transmittal of search copy delayed until search fee is paid	✓	

FOR INTERNATIONAL BUREAU USE ONLY

11-1	Date of receipt of the record copy by the International Bureau	
------	--	--

SC/cw 030233WO
APRIL 16, 2003

5 Protocol Parameter Re-Negotiation after certain Types of
Non-Transparent Data Call Handovers

DESCRIPTION

10 The invention relates to a method for negotiation or re-
negotiation of a parameter or parameters for use in the
operation of a protocol that controls data transmission
between first Communication Units (CUs) and third CUs via
second CUs, where the protocol is operated by protocol
15 entities in the first and third CUs, where a first CU is
always associated with a second CU at a time, where a
second CU is always associated with a third CU at a time,
and where there exist second CUs of at least a first and
second type and/or third CUs of at least a first and
20 second type that require different choices of said
parameter.

In mobile radio systems of the second and third
generation, such as the Global System for Mobile
25 Communications (GSM) and the Universal Mobile
Telecommunications System (UMTS), Non-Transparent (NT)
data bearers are provided that offer an error-free data
transfer service to the user. The data transfer service
is based on the Radio Link Protocol (RLP) and the Layer-2
30 Relay (L2R) Character Oriented Protocol (COP). The RLP
function offers an Automatic Repeat Request (ARQ)
protocol that extends from the mobile station (MS) to the
network Interworking Functions (IWF) in the Mobile-
services Switching Centre (MSC) in order to detect errors
35 by means of a Forward Error Correction (FEC) procedure
and RLP's Frame Check Sequence (FCS) for each transmitted

- 2 -

RLP frame, where an RLP frame represents an RLP Protocol Data Unit (PDU), and to eliminate errors by repeating the transmission of the frame under exploitation of the time-variance of the transmission medium. The L2R function
5 converts the layer-2 protocol of the MS into a COP that uses transmission protected by an RLP.

The RLP is controlled by several parameters such as acknowledgement, reply and re-sequencing timers or the
10 number of retransmission attempts or required window sizes, that either are assigned default values or can be modified by the user or network e.g. by means of AT commands. If a change of parameters is initiated in either the MS RLP entity or the MSC RLP entity, the
15 desired parameters are signalled to the corresponding peer RLP entity via eXchange IDentification (XID) frames, which are RLP frames (PDUs) in which the information field is interpreted as exchange identification instead of data. To start negotiation, an XID command frame will
20 be signalled. The peer entity confirms the value of each parameter by returning the value within an XID response or offering lower or higher values of the parameter in its place depending on the sense of negotiation of the parameter.

25 The RLP may use one physical link (single-link) or from 1 up to 4 sub-streams on one or more physical links (multi-link). The multi-link version of the RLP protocol is only applicable in GSM and not in UMTS.

30 Among said control parameters of the RLP protocol, the acknowledgement timer T1 associated with the transmitting RLP entity indicates the re-transmission period after

- 3 -

which the re-transmission of a not-acknowledged frame may be started. Due to ARQ in combination with FEC, each received RLP frame is checked for correct/incorrect reception at the receiving RLP entity, and

5 correct/incorrect reception is signalled back to the transmitting peer RLP entity. The timer T1 defines the maximum time period starting with the transmission of an RLP frame within which a correct/incorrect acknowledgement of the transmitted RLP frame is expected.

10 An expiration of the timer T1 causes the retransmission of the frame because the acknowledgement of the sent frame was not received in time.

Among said control parameters of the RLP protocol, the

15 timer T2 associated with the receiver indicates the maximum permissible period the receiving RLP peer entity is allowed between the reception of a frame and the transmission of the acknowledgement message.

20 Among said control parameters of the RLP protocol, the re-sequencing timer T4 guards the maximum difference between the delays of frames transmitted on different physical links within the multi-link RLP protocol. The timer T4 defines how great the variation of the

25 transmission delay of all physical links can be. If received frames are out of sequence, the receiver waits for the duration of timer T4 for the missing frames before starting any recovery actions.

30 Concluding, in multi-link operation (e.g. GSM), $T1 > T2 + T4 + 2 \cdot TD$ has to hold, where TD is the transmission delay between MS and MSC, whereas in single-link transmission (e.g. UMTS), $T1 > T2 + 2 \cdot TD$ has to hold.

- 4 -

In both GSM and UMTS, the transmission of the PDUs/frames of the RLP is performed by lower layers of the protocol stack. The delay characteristics of the RLP frames are thus at least dependent on the delay characteristics of the physical layer, i.e. the lowest layer in the protocol stack. When considering the transmission of RLP PDUs from an MS RLP entity to an MSC RLP entity in GSM, in the physical layer the transmission paths between the MS and the Base Transceiver Station (BTS), between the BTS and the Base Station Controller (BSC) and between the BSC and the MSC have to be taken into account. In UMTS, basically the same propagation paths are encountered, where the MS corresponds to the User Equipment (UE), the BTS corresponds to the Node B and the BSC corresponds to the Radio Network Controller (RNC). In the sequel, GSM notation will be used to identify the components of both mobile radio systems.

The BTS-BSC and BSC-MSC interfaces are usually realised by lower-delay connections such as Time Division Multiplex (TDM) connections (e.g. ISDN primary rate). However, also higher-delay connections such as Internet Protocol (IP), e.g. in a Distributed Radio Access Network (DRAN) environment or in an IP-based GSM Intranet Office (GIO) environment, or satellite connections may be applicable. It is easily understood that depending on the delay characteristics of the BTS-BSC or BSC-MSC connection, especially the timers T1 and T4 of the RLP have to be adapted accordingly to assure proper operation of the mobile radio system.

- 5 -

The applicant's international patent application WO 02/25888 A2 discloses one approach for an adaptation of RLP timers. WO 02/25888 A2 sets out from the fact that, in a typical GSM physical link, the transmission delay is within a tightly bounded range so that the RLP entities will use default values for the RLP timers based on the expected characteristics of the physical link. For the case when unexpectedly large delays occur, as e.g. in an IP-based GSM office environment, an XID proxy unit is proposed as additional negotiation unit that monitors and verifies XID commands sent between the MS and MSC entities. The XID proxy has knowledge of the maximum delay values for the physical link between the MS and the MSC. Based on this information, it has the capacity to intervene in the process of negotiation of T1 timer values between the MS and the MSC with the aim of ensuring that the value that is settled upon is large enough to cope with transmission delays that might be beyond the expectations (the default or offered timer values) of the MS and MSC.

In this prior art approach, the XID proxy is only activated when it "sniffs" the passing of an XID negotiation message between the RLP entities of the MS and the MSC. For this to happen, it is required that a new NT data call is set up within the higher-delay network, so that standard RLP timer negotiation between the RLP entities of MS and MSC is initiated via XID frames.

However, the prior art approach fails to adapt the RLP parameters to the delay characteristics of a higher-delay network if the NT data call was set up - and thus

- 6 -

parameterised with a smaller timer during the initial RLP timer negotiation - in a lower-delay network and is subsequently handed over to the higher delay network, where no re-negotiation of the RLP timers takes place and thus the XID proxy is not activated. Such a situation occurs if a MS is associated with a first BTS that is connected to its MSC via TDM, and then is handed over to a BTS that is connected to its MSC via IP (where both MSCs can well be the same).

10

A similar problem arises when a hand-over of a UMTS-based NT data call to a GSM-based call occurs and RLP parameters that are essential in the GSM system, but not essential in the UMTS system, e.g. the RLP timer T4, are not negotiated or re-negotiated upon entry in the GSM system, so that default values are used in the GSM system instead of using values that have been adapted or selected for particular use in the GSM system.

20 In view of the above-mentioned problems, it is thus the object of the present invention to provide a method for improved protocol parameter adaptation for certain types of non-transparent data call handovers.

25 To solve the object of the invention, it is proposed that a method for negotiation or re-negotiation of a parameter for use in the operation of a protocol that controls data transmission between first Communication Units (CUs) and third CUs via second CUs, where the protocol is operated by protocol entities in the first and third CUs, where a first CU is always associated with a second CU at a time, where a second CU is always associated with a third CU at a time, and where there exist second CUs of at least a

- 7 -

first and second type and/or third CUs of at least a first and second type that require different choices of said parameter, is characterised in that when an existing association of said first CU with a former second CU is changed to an association of said first CU with a new second CU, said protocol entities of the first CU and said protocol entities of the third CU associated with the new second CU exchange at least one negotiation message containing a value for said parameter. Thus when the association of the first CU to the second CU is changed, either resulting in an exchange of the type of the second CU in the chain first-second-third CU from a former second CU of a first type to a new second CU of a second type when both the former and new second CU are associated with the same third CU (of any type), or resulting in an exchange of the type of the third CU in the chain first-second-third CU when the former second CU and the new second CU are of the same type, but associated with different third CUs of a first and second type, respectively, or resulting in an exchange of the types of both the second and the third CU in the chain first-second-third CU, when the former and new second CUs of the first and second type are associated with different third CUs of a first and second type, or resulting in no exchange of the types of the second and third CUs in the chain first-second-third CU, when the former second CU is of the same type as the new second CU and if both second CUs are associated with the same type of third CU, either the protocol entity of the first or third CU are informed of the change of associations and are triggered to transmit a negotiation message to their corresponding peer entity. The negotiation message represents a proposal to change a parameter, which

- 8 -

affects the performance of the protocol controlling the data transmission between the first and third CU via the second CU and which depends on the type of second and/or third CU used in the chain first-second-third CU. The influence of the parameter on the protocol may as well be seen in the fact that the parameter is not required, when a third CU of the first type is part of the chain first-second-third CU, but is required when the third CU of the first type is replaced by a third CU of the second type.

10

A first preferred embodiment of the invention is characterised in that the former second CU was associated with a third CU of a first type and the new second CU is associated with a third CU of a second type. The type of the third CU in the chain first-second-third CU thus changes from a first type to a second type. In said event of a change of the third CU from a first type to a second type, an additional change of the type of the second CU from a first type to a second type may occur or not.

20

According to the first preferred embodiment of the invention, it is preferred that in said exchange of at least one negotiation message, the protocol entity in the first CU performs the following steps: a first step of checking whether said parameter is required for the operation of said protocol between the protocol entities of the first CU and the third CU that is associated to the new second CU, a second step of checking whether a value for said parameter needs to be negotiated or renegotiated, and a third step of transmitting a negotiation message containing a value for said parameter to the protocol entity of the third CU associated with the new second CU, if said first and second checking

30

- 9 -

steps produced positive results. The parameter is thus only negotiated or re-negotiated within the protocol if it is required for the operation of said protocol between the protocol entities of the first CU and the third CU that is associated to the new second CU, a fact that may mainly depends on the type of third CU. Elsewhere, both protocol entities in the first and third CU use a default value for the parameter, and negotiation or re-negotiation is not necessary but may still be carried out. The initiative for parameter negotiation or re-negotiation can as well be started by the protocol entity of the third CU. Then, however, no values for the parameter as selected by the user can serve as a basis for starting the parameter negotiation/re-negotiation.

In said exchange of at least one negotiation message in the first embodiment of the invention, the protocol entity of the third CU associated with the new second CU performs the following steps: receiving the negotiation message transmitted by the protocol entity of the first CU containing a value for said parameter, and transmitting a negotiation message to the protocol entity of the first CU containing the received or a higher value for said parameter.

The first embodiment of the present invention is advantageously characterised in that said first CU is a Mobile Station (MS) of a mobile radio system, that said second CUs are Base Transceiver Stations (BTSs), and that said third CUs are Mobile-services Switching Centres (MSCs). The invention thus is for instance applicable to GSM systems and UMTS systems. In the MSCs, the protocol entities are operated by the Interworking Function (IWF).

- 10 -

In the physical link between BTS and MSC, furthermore a Base Station Controller (BSC) may be provided.

According to the first embodiment of the present invention, it is further preferred that said third CU of the first type is a MSC of a mobile network operated according to the UMTS standard or a derivative thereof (UMTS-MSC), and that said third CU of the second type is a MSC of a mobile network operated according to the GSM standard or a derivative thereof (GSM-MSC). With the change of an association of the MS with a former BTS that is associated with a UMTS-MSC, to an association of the MS to a new BTS that is associated with a GSM-MSC, a handover of the MS from a UMTS system to a GSM system occurs, and a negotiation or re-negotiation of parameters, which are not required for said protocol when running in the UMTS system, may be necessary to properly operate the protocol in the GSM system.

According to the first embodiment of the invention, it is preferred that said protocol is a circuit switched, non-transparent single- and/or multi-link data protocol with Automatic Repeat Request (ARQ).

According to the first embodiment of the invention, it is further preferred that said protocol is the Radio Link Protocol (RLP). Within the RLP protocol, eXchange IDentification (XID) messages then can be used as negotiation messages.

Said parameter then preferably defines the value of a re-sequencing timer that guards the difference between the

- 11 -

delays of frames transmitted on different physical links within a multi-link protocol.

Said first step of checking whether said parameter is
5 required for the operation of said protocol between the
protocol entities of the first CU and the third CU that
is associated to the new second CU then comprises the
step of checking whether the data transmission between
the MS and the GSM-MSC is a multi-link transmission or
10 whether there is a possibility that the single-link
transmission will be upgraded to a multi-link
transmission later. In single-link transmission, the re-
sequencing timer is purposeless (zero) and thus does not
have to be re-negotiated upon entry of the MS into the
15 GSM cell.

Said second step of checking whether said parameter needs
to be negotiated or re-negotiated comprises the step of
checking whether a value for said re-sequencing timer was
20 defined by the user of the MS.

If no value was defined by the user, default values for
the re-sequencing timer as stored in the RLP entities of
both the MS and GSM-MSC may be used, and no negotiation or
re-negotiation was necessary.

25

A second preferred embodiment of the invention is
characterised in that the former second CU is a second CU
of a first type and the new second CU is a second CU of a
second type. Thus when an association of the first CU
30 with a former second CU changes to an association of the
first CU with a new second CU, the type of the second CU
in the chain first-second-third CU changes from a second
CU of a first type to a second CU of a second type. Note

- 12 -

that, depending on the association of the second CUs with their third CUs, an additional change of the type of the third CU from a first type to a second type may occur as well.

5

In said exchange of at least one negotiation message in the second embodiment of the invention, the protocol entity of the third CU associated with the new second CU performs the step of transmitting a negotiation message
10 containing a value for said parameter to the protocol entity of the first CU. However, the initiation of the parameter re-negotiation may as well be started by the protocol entity of the first CU.

15 According to the second embodiment of the invention, it is preferred that said value for said parameter depends on the transmission characteristic of the transmission medium between the new second CU and its associated third CU and that said value can be determined by said third CU
20 for each of the second CUs it can be associated with. This can either be achieved by measurements of the transmission characteristics that are initiated by the third CU or by a look-up table that is stored at the third CU and contains the values for each possible
25 association of the third CU with second CUs, where the transmission characteristic of the medium between second and third CU also contains the influence of the BSC.

In said exchange of at least one negotiation message in
30 the second embodiment, the protocol entity of the first CU preferably performs the following steps: receiving the negotiation message transmitted by the protocol entity of the third CU that is associated with the new second CU

- 13 -

and containing a value for said parameter, and transmitting a negotiation message to the protocol entity of the third CU that is associated with the new second CU containing the same or a higher value for said parameter.

- 5 Thus the value for said parameter is up-negotiated based upon a value for said parameter that is proposed by the third CU.

10 According to the second embodiment of the invention, it is preferred that said first CU is a Mobile Station (MS) of a mobile radio system, that said second CUs are Base Transceiver Stations (BTSs), and that said third CUs are Mobile-services Switching Centres (MSCs). The invention thus is for instance applicable to GSM systems and UMTS
15 systems. In the MSCs, the protocol entities are operated by the Interworking Function (IWF). In the physical link between BTS and MSC, furthermore a Base Station Controller (BSC) may be provided.

- 20 According to the second embodiment of the invention, it is further preferred that one out of the first and second types of said second CU is a BTS that is connected to its associated MSC via a lower-delay network, and that the other type of said second CU is a BTS that is connected
25 to its associated MSC via a higher-delay network. The method according to the second embodiment of the present invention aims at the re-negotiation of a parameter, which influences the performance of the protocol controlling the data transmission between MS and MSC and
30 which is affected by a change from a BTS and related network with a lower delay to a BTS and related network with a higher delay or vice versa from a BTS and related

- 14 -

network with a higher delay to a BTS and related network with a lower delay.

Said lower-delay network may be a Time Division Multiplex
5 (TDM) network.

Said higher-delay network may be at least partially based on the Internet Protocol (IP) or a satellite connection. E.g. the connection between BTS and BSC may be IP-based,
10 and the connection from the BSC to the MSC may be TDM-based.

According to the second embodiment of the invention, the MSC that is connected to its associated BTS via the
15 lower-delay network may either be operated according to the UMTS standard, the GSM standard or a derivative thereof, and the MSC that is connected to its associated BTS via the higher-delay network may either be operated according to the UMTS standard, the GSM standard or a
20 derivative thereof.

According to the second embodiment of the invention, it is preferred that said protocol is a circuit switched, non-transparent single- and/or multi-link data protocol
25 with Automatic Repeat Request (ARQ).

According to the second embodiment of the invention, it is further preferred that said protocol is the Radio Link Protocol (RLP). Within the RLP protocol, eXchange
30 IDentification (XID) messages then can be used as negotiation messages.

- 15 -

- Said parameter advantageously defines the value of an acknowledgement timer that guards the re-transmission period after which the re-transmission of a not-acknowledged frame within a protocol with ARQ may be started. This parameter extremely depends on the delay characteristics of the physical link between MS and MSC, which incorporates the link between BTS and BSC and BSC and MSC.
- 10 Said parameter further advantageously defines the value of a re-sequencing timer that guards the difference between the delays of frames transmitted on different physical links within a multi-link protocol. If the handover takes place within the GSM system or from the
- 15 UMTS system into the GSM system, multi-link data transmission or single-link data transmission that may later be upgraded to multi-link transmission, e.g. within the RLP protocol, is possible, and a re-sequencing timer is required. As the acknowledgement timer, the re-
- 20 sequencing timer extremely depends on the delay characteristics of the physical link between MS and MSC, which incorporates the link between new BTS and BSC and BSC and MSC.
- 25 Said transmission characteristic is preferably related to the transmission delay. The MSC then administrates a look-up table that contains the delays (or maximum delay difference in case of multi-link transmission) for each BTS that it may become associated with, and in case of a
- 30 change of a lower-delay BTS to a higher-delay BTS or vice versa in the chain MS-BTS-(BSC)-MSC proposes a suited value for said acknowledgement or re-sequencing timer to

- 16 -

the MS, where said value is taken from that look-up table.

The object of the invention is further solved by a method
5 for negotiation of a parameter or parameters for use in
the operation of a protocol that controls data
transmission between first Communication Units (CUs) and
third CUs via second CUs, where the protocol is operated
by protocol entities in the first and third CUs, where a
10 first CU is always associated with a second CU at a time,
where a second CU is always associated with a third CU at
a time, and where there exist second CUs of at least a
first and second type and/or third CUs of at least a
first and second type that require different choices of
15 said parameter, which is characterised in that in the
case that it is possible that an association of said
first CU with a second CU that is associated with a third
CU of a first type may be changed to an association of
said first CU with a second CU that is associated with a
20 third CU of a second type, said protocol entities of said
first CU and said protocol entities of said third CU of
the first type perform the step of exchanging at least
one negotiation message containing a value for said
parameter prior to said change of associations.

25

In the sequel, this solution will be referred to as third
embodiment of the present invention. If it is possible
that a change of the third CU in the chain first-second-
third CU occurs from a third CU of a first type to a
30 third CU of a second type, wherein in the former case,
the parameter is not required for said protocol, but in
the latter case, said parameter is required for said
protocol, it makes sense to negotiate said parameter

between the protocol entities of the first CU and the protocol entities of the third CU of the first type, i.e. before the change of associations occurs. Parameter negotiation may be initiated by either the first of third
5 CU by proposing a value for said parameter. The negotiated value for said parameter is then stored in the protocol entities of the first CU and the third CU of the first type, but is not used in the operation of said
10 protocol. When the third CU of the first type in the chain first-second-third CU is changed to a third CU of a second type, said value for the parameter is handed from the third CU of the first type to the third CU of the second type, unless the third CU of the first type and the third CU of the second type have a common part, e.g.
15 an interworking function for the case that the third CUs are MSCs of mobile networks operated according to different standards such as UMTS and GSM, wherein said common part maintains the association with the first CU and holds said value for the parameter during the change
20 of the third CU in the chain first-second-third CU. Thus parameter re-negotiation between the first CU and the third CU of the second type after the change of associations is not necessary, because the required value for the parameter is already available in both protocol
25 entities.

According to the third embodiment of the present
30 invention, it is advantageous that in said exchange of at least one negotiation message, the protocol entities in the first CU or the third CU of the first type perform the following steps: checking whether it is possible that

- 18 -

said data transmission between the first CU and the third CU of the second type is a multi-link data transmission that requires the definition of a re-sequencing timer as said parameter for said protocol, and checking whether a value for said re-sequencing timer is available as a basis for negotiation.

E.g., when the first CU is a MS of a mobile radio system, the second CUs are BTSs and the third CUs are MSCs of a mobile network operated according to the UMTS standard (third CU of the first type) and GSM standard (third CU of the second type), parameter negotiation then only takes place if the future call in the GSM system is possibly a multi-link call, because otherwise the re-sequencing timer would not be required. As a basis for parameter negotiation, a value for the parameter as selected by the user of the MS or default values as stored in the UMTS-MSC or the MS may be used.

The object of the invention is further solved by a computer program product directly loadable into the internal memory of a digital computer, comprising software code portions for performing the steps as performed by the protocol entities of the first and third CUs when said product is run on a computer.

The object of the invention is further solved by a system for data transmission between first Communication Units (CUs) of said system and third CUs of said system via second CUs of said system, where the protocol that controls said data transmission is operated by protocol entities in the first and third CUs, where a first CU is always associated with a second CU at a time, where a

- 19 -

second CU is always associated with a third CU at a time,
and where there exist second CUs of at least a first and
second type and/or third CUs of at least a first and
second type that require different choices of at least
5 one parameter for use in the operation of said protocol,
which is characterised in that when an existing
association of said first CU with a former second CU is
changed to an association of said first CU with a new
second CU, said protocol entities of the first CU and
10 protocol entities of the third CU associated with the new
second CU exchange at least one negotiation message
containing a value for said parameter.

15 The object of the invention is further solved by a system
for data transmission between first Communication Units
(CUs) of said system and third CUs of said system via
second CUs of said system, where the protocol that
controls said data transmission is operated by protocol
20 entities in the first and third CUs, where a first CU is
always associated with a second CU at a time, where a
second CU is always associated with a third CU at a time,
and where there exist second CUs of at least a first and
second type and/or third CUs of at least a first and
25 second type that require different choices of at least
one parameter for use in the operation of said protocol,
which is characterised in that in the case that it is
possible that an association of said first CU with a
second CU that is associated with a third CU of a first
30 type may be changed to an association of said first CU
with a second CU that is associated with a third CU of a
second type, said protocol entities of said first CU and
said protocol entities of said third CU of the first type

- 20 -

perform the step of exchanging at least one negotiation message containing a value for said parameter prior to said change of associations.

5 These and other aspects of the invention will be apparent from and elucidated with reference to the embodiments described hereinafter. In the figures show:

10 Fig. 1 an example scenario for the application of the first and third embodiment of the present invention,

Fig. 2 a signalling chart according to the example of
15 the first embodiment of the present invention according to Fig. 1,

Fig. 3 an example scenario for the application of the
20 second embodiment of the present invention,

Fig. 4 a signalling chart according to the example of
the second embodiment of the present invention according to Fig. 3, and

25 Fig. 5 a signalling chart according to the example of the third embodiment of the present invention according to Fig. 1.

Fig. 1 depicts an example for the application of the
30 first and third embodiment of the present invention. A user 1 that represents a MS is located in the coverage area of a UMTS cell 2, which is associated with a UMTS-
MSC, and creates an NT data call. The data call is

configured via AT commands that are depicted enlarged on the display 3 of the users communication equipment. In particular, the user requests a Fixed Network User Rate (FNUR) of 56 kbps with AT command +CBST, changes the RLP parameter timer T4 to be 60 ms with AT command +CRLP and initiates the call with the command ATD<number>. Call set-up starts, and the RLP entity of the MS negotiates its connection parameters by sending an XID command frame to the peer RLP entity in the UMTS-MSC.

10

According to the first embodiment of the present invention, the timer T4 is not negotiated, because it is purposeless in UMTS and has therefore to be ignored. However, the timer T4 as selected by the user of the MS 1 is stored in the protocol entity of the MS 1. The RLP entity at the UMTS-MSC confirms the parameters proposed by sending an XID response frame back to the RLP entity of the MS. After a while, the user sees a CONNECT on the screen indicating that the connection is ready for data transfer and starts data transfer.

20

During the data transfer, the user 1 leaves the coverage area of the UMTS cell, and the NT data call is handed to a GSM cell 4 that is associated with a GSM-MSC.

25

In this particular case, the resulting call in GSM is a multi-slot call, so that RLP timer T4 is required. In a prior art system, both RLP entities of the MS and the GSM-MSC would start using default values for the timer T4. In contrast, according to the first embodiment of the present invention, parameter T4 is re-negotiated between MS and GSM-MSC upon entry in the GSM cell, so that the timer T4, which was set to 60 ms by the user during call

30

- 22 -

set-up in the UMTS cell, is considered within the RLP of the GSM cell.

Fig. 2 depicts a corresponding signalling chart between the RLP entities 5 in the MS and the RLP entities 6 in the MSC for the case of a system handover between UMTS and GSM, as exemplarily introduced in Fig. 1. After call set-up in the UMTS cell, data transfer 7 is started between the RLP entities 5 and 6 based on the RLP protocol. The event of a handover of the NT data call from a UMTS-MSC to an GSM-MSC is indicated to the RLP entity 5 of the MS by means of an indication 8. The RLP entity 5 then transmits an XID command frame 10 with the value T4 as pre-selected by the user to its peer RLP entity 6 in the GSM-MSC, which accepts or further increases the proposed value of the timer T4 by transmitting an XID response message 11. Thus the timer T4 is re-negotiated upon entry in the GSM cell, and further data transfer 12 can start based on a multi-link transmission with re-sequencing timer T4=60ms.

Fig. 3 depicts an example scenario for the application of the second embodiment of the present invention. A MS 13 is located in the coverage area of a first BTS 14 and sets up a NT multi-link GSM data call. BTS 14 is connected to a BSC via a TDM-based connection 16. The BSC 15 in turn is connected to a GSM-MSC 17 via a second TDM-based connection 18. The network between BTS 14 and GSM-MSC 17 thus is entirely TDM-based. The MS 13 then moves out of the coverage area of BTS 14 and moves into the coverage area of BTS 19, so that an intra-MSC handover occurs. BTS 19 is connected to a BSC 20 via an IP-based connection 21, and the BSC 20 is connected to the same

- 23 -

MSC 17 as BSC 15 via a TDM-based connection 22. The network between BTS 19 and GSM-MSC 17 thus is partially IP-based. Due to the IP-based connection 21, the delay and the delay variation of the frame/PDUs transmitted within the RLP protocol is significantly higher when MS 5 13 is associated with BTS 19 as compared to the case when MS 13 is associated with BTS 14. In prior art, the timers T1 and T4 are not automatically re-negotiated after such a handover, and default values for the timers T1 and T4, 10 which are optimised for TDM-based connections between the BTS and the GSM-MSC, are adopted by the RLP entities in the MS and GSM-MSC. In contrast, according to the second embodiment of the present invention, suited values for the timers T1 and T4 are stored in the MSC and are 15 automatically re-negotiated upon entry of the MS 13 into the cell which is operated by the partially IP-based network.

Fig. 4 depicts a corresponding signalling chart between 20 the RLP entities 23 in the MS and the RLP entities 24 in the GSM-MSC for the case of a system handover between a lower-delay TDM-based network and a higher-delay partially IP-based network as introduced in Fig. 3. After call set-up in the lower-delay network, data transfer 25 is started between the RLP entities 23 and 24 based on the RLP protocol. The event of a handover of the NT data call from the lower-delay network with BTS 14 to a higher-delay network with BTS 19 is indicated to the RLP entity 24 of the GSM-MSC by means of an indication 26. 30 The RLP entity 24 in the GSM-MSC then transmits an XID command frame 28 with the value T1 as stored in the GSM-MSC for the connection between GSM-MSC and associated BTS 19 to its peer RLP entity 23 in the MS, which accepts or

- 24 -

further increases the proposed value of the acknowledgement timer T1 by transmitting an XID response message 29. The same re-negotiation takes place for the re-sequencing timer T4 via XID command 30 transmitted by the RLP entity 24 in the GSM-MSC and XID response 31 transmitted by the RLP entity 23 in the MS. Both parameters can be re-negotiated also with a single XID command/response pair. Thus both timers T1 and T4 are re-negotiated upon entry in the higher-delay network, and data transfer 32 in the higher-delay network becomes possible.

Fig. 5 depicts a signalling chart between the RLP entities 33 in the MS and the RLP entities 34 in the MSC for the case of a data call handover between UMTS and GSM (cf. the scenario of Fig. 1) and for the case that the third embodiment of the present invention is used to adapt protocol parameters to the handover prior to the actual handover. During call set-up in the UMTS cell 2, the parameter T4 as pre-selected by the user of the MS 1 is negotiated in view of a possible future handover to a GSM cell 4. To this aim, the MS RLP entity 33 transmits an XID command frame 35 with the value T4 as pre-selected by the user of MS 1 (T4=60ms) to its peer UMTS-MSC RLP entity 34, which accepts or further increases the proposed value of the timer T4 by transmitting an XID response message 36. The negotiated value for the parameter T4 is then stored in the RLP entities of both MS 33 and UMTS-MSC 34, but is not used in the RLP protocol within the UMTS system. Then data transfer 37 is started between the RLP entities 33 and 34 based on the RLP protocol. After a handover 38 of the MS 1 from the UMTS cell 2 to the GSM cell 4, data transfer 39 between

- 25 -

the MS RLP entity 33 and the GSM-MSC RLP entity 34 starts without parameter re-negotiation. However, due to the fact that the re-sequencing timer T4 is relevant for the RLP protocol in the GSM system, the value for T4 as
5 available in the MS RLP entity 33 and in the GSM-MSC RLP entity 34 is used in the GSM RLP protocol. The value for T4 is available in both the UMTS-MSC and the GSM-MSC RLP entities despite the fact that a handover occurred from the UMTS-MSC to the GSM-MSC, because the same
10 interworking function (IWF) with the RLP entity that has been reserved at the setup of the call will be used throughout the entire call. I.e., even after a handover, the same IWF is still used.

15 The invention has been described above by means of preferred embodiments. It should be noted that there are alternative ways and variations which are obvious to a skilled person in the art and can be implemented without deviating from the scope and spirit of the appended
20 claims, e.g. the direction of the change of the parameter values in the negotiation may be upwards or downwards depending on the meaning of the parameter being negotiated.

25

30

35

- 26 -

SC/cw 030233WO
March 26, 2003

CLAIMS

5

1. Method for negotiation or re-negotiation of a
parameter or parameters for use in the operation of a
protocol that controls data transmission between first
Communication Units (CUs) and third CUs via second CUs,
10 where the protocol is operated by protocol entities in
the first and third CUs,
where a first CU is always associated with a second CU at
a time,
where a second CU is always associated with a third CU at
15 a time, and
where there exist second CUs of at least a first and
second type and/or third CUs of at least a first and
second type that require different choices of said
parameter,

20

characterised in that

when an existing association of said first CU with a
former second CU is changed to an association of said
25 first CU with a new second CU,
said protocol entities of the first CU and protocol
entities of the third CU associated with the new second
CU exchange at least one negotiation message containing a
value for said parameter.

30

2. Method according to claim 1,
characterised in that

- 27 -

the former second CU was associated with a third CU of a first type and the new second CU is associated with a third CU of a second type.

5 3. Method according to claim 2,
characterised in
that in said exchange of at least one negotiation
message, the protocol entity in the first CU performs the
following steps:

10

a first step of checking whether said parameter is
required for the operation of said protocol between the
protocol entities of the first CU and the third CU that
is associated to the new second CU,

15

a second step of checking whether said parameter needs to
be negotiated or re-negotiated, and

a third step of transmitting a negotiation message
20 containing a value for said parameter to the protocol
entity of the third CU associated with the new second CU,
if said first and second checking steps produced positive
results.

25

4. Method according to claim 3,
characterised in
that in said exchange of at least one negotiation
message, the protocol entity of the third CU associated
30 with the new second CU performs the following steps:

- 28 -

receiving the negotiation message transmitted by the protocol entity of the first CU containing a value for said parameter, and

5 transmitting a negotiation message to the protocol entity of the first CU containing the received or a higher value for said parameter.

5. Method according to any of the claims 1-4,
10 characterised in

that said first CU is a Mobile Station (MS) of a mobile radio system,

15 that said second CUs are Base Transceiver Stations (BTSs), and

that said third CUs are Mobile-services Switching Centres (MSCs).

20
6. Method according to claim 5,
characterised in

that said third CU of the first type is a MSC of a mobile
25 network operated according to the UMTS standard or a derivative thereof (UMTS-MSC), and

that said third CU of the second type is a MSC of a mobile network operated according to the GSM standard or
30 a derivative thereof (GSM-MSC).

7. Method according to any of the claims 5-6,
characterised in

- 29 -

that said protocol is a circuit switched, non-transparent single- and/or multi-link data protocol with Automatic Repeat Request (ARQ).

5 8. Method according to claim 7,
characterised in

that said protocol is the Radio Link Protocol (RLP).

9. Method according to any of the claims 7-8,
10 characterised in
that said parameter defines the value of a re-sequencing timer that guards the difference between the delays of frames transmitted on different physical links within a multi-link protocol.

15
10. Method according to any of the claims 7-9,
characterised in
that said first step of checking whether said parameter is required for the operation of said protocol between
20 the protocol entities of the MS and GSM-MSC comprises the step of checking whether the data transmission between the MS and the GSM-MSC is a multi-link transmission or whether there is a possibility that the single-link transmission will be upgraded to a multi-link
25 transmission later.

11. Method according to claim 10,
characterised in
that said second step of checking whether said parameter
30 needs to be negotiated or re-negotiated comprises the step of checking whether a value for said re-sequencing timer was defined by the user of the MS.

12. Method according to claim 1,

- 30 -

characterised in that

the former second CU is a second CU of a first type and
the new second CU is a second CU of a second type.

5 13. Method according to claim 12,
characterised in

that in said exchange of at least one negotiation
message, the protocol entity of the third CU associated
with the new second CU performs the step of transmitting
10 a negotiation message containing a value for said
parameter to the protocol entity of the first CU.

14. Method according to claim 13,
characterised in

15 that said value for said parameter depends on the
transmission characteristic of the transmission medium
between the new second CU and its associated third CU and

20 that said value can be determined by said third CU for
each of the second CUs it can be associated with.

15. Method according to any of the claims 13-14,
characterised in

25 that in said exchange of at least one negotiation
message, the protocol entity of the first CU performs the
following steps:

receiving the negotiation message transmitted by the
30 protocol entity of the third CU that is associated with
the new second CU and containing a value for said
parameter, and

- 31 -

transmitting a negotiation message to the protocol entity of the third CU that is associated with the new second CU containing the same or a higher value for said parameter.

5 16. Method according to any of the claims 12-15,
characterised in

that said first CU is a Mobile Station (MS) of a mobile
radio system,

10

that said second CUs are Base Transceiver Stations
(BTSs), and

that said third CUs are Mobile-services Switching Centres
15 (MSCs).

17. Method according to claim 16,
characterised in

20 that one out of the first and second types of said second
CU is a BTS that is connected to its associated MSC via a
lower-delay network, and

that the other type of said second CU is a BTS that is
25 connected to its associated MSC via a higher-delay
network.

18. Method according to claim 17,
characterised in

30 that said lower-delay network is a Time Division
Multiplex (TDM) network.

19. Method according to any of the claims 17-18,

- 32 -

characterised in

that said higher-delay network is at least partially based on the Internet Protocol (IP) or a satellite connection.

5

20. Method according to any of the claims 17-19, characterised in

10 that the MSC that is connected to its associated BTS via a lower-delay network is either operated according to the UMTS standard, the GSM standard or a derivative thereof, and

15 that the MSC that is connected to its associated BTS via a higher-delay network is either operated according to the UMTS standard, the GSM standard or a derivative thereof.

20 21. Method according to any of the claims 12-20, characterised in

that said protocol is a circuit switched, non-transparent single- and/or multi-link data protocol with Automatic Repeat Request (ARQ).

25 22. Method according to claim 21, characterised in

that said protocol is the Radio Link Protocol (RLP).

30 23. Method according to any of the claims 21-22, characterised in

that said parameter defines the value of an acknowledgement timer that guards the re-transmission period after which the re-transmission of a not-

- 33 -

acknowledged frame within a protocol with ARQ may be started.

24. Method according to any of the claims 21-22,
5 characterised in
that said parameter defines the value of a re-sequencing timer that guards the difference between the delays of frames transmitted on different physical links within a multi-link protocol.

10

25. Method according to any of the claims 14-24,
characterised in
that said transmission characteristic is related to the transmission delay.

15

26. Method for negotiation of a parameter or parameters for use in the operation of a protocol that controls data transmission between first Communication Units (CUs) and third CUs via second CUs,
20 where the protocol is operated by protocol entities in the first and third CUs,
where a first CU is always associated with a second CU at a time,
where a second CU is always associated with a third CU at
25 a time, and
where there exist second CUs of at least a first and second type and/or third CUs of at least a first and second type that require different choices of said parameter,

30

characterised in that

- 34 -

in the case that it is possible that an association of
said first CU with a second CU that is associated with a
third CU of a first type may be changed to an association
of said first CU with a second CU that is associated with
5 a third CU of a second type,
said protocol entities of said first CU and said protocol
entities of said third CU of the first type perform the
step of exchanging at least one negotiation message
containing a value for said parameter prior to said
10 change of associations.

27. Method according to claim 26,
characterised in
that in said exchange of at least one negotiation
15 message, the protocol entities in the first CU or the
third CU of the first type perform the following steps:

checking whether it is possible that said data
transmission between the first CU and the third CU of
20 the second type is a multi-link data transmission that
requires the definition of a re-sequencing timer as said
parameter for said protocol, and

checking whether a value for said re-sequencing timer is
25 available as a basis for negotiation.

28. A computer program product directly loadable into the
internal memory of a digital computer, comprising
software code portions for performing the steps of any of
30 the claims 3, 4, 10, 13, 14, 15, 26 and 27 when said
product is run on a computer.

- 35 -

29. System for data transmission between first
Communication Units (CUs) of said system and third CUs of
said system via second CUs of said system,
where the protocol that controls said data transmission
5 is operated by protocol entities in the first and third
CUs,
where a first CU is always associated with a second CU at
a time,
where a second CU is always associated with a third CU at
10 a time, and
where there exist second CUs of at least a first and
second type and/or third CUs of at least a first and
second type that require different choices of at least
one parameter for use in the operation of said protocol,
15 characterised in that

when an existing association of said first CU with a
former second CU is changed to an association of said
20 first CU with a new second CU,
said protocol entities of the first CU and protocol
entities of the third CU associated with the new second
CU exchange at least one negotiation message containing a
value for said parameter.

25 30. System for data transmission between first
Communication Units (CUs) of said system and third CUs of
said system via second CUs of said system,
where the protocol that controls said data transmission
30 is operated by protocol entities in the first and third
CUs,
where a first CU is always associated with a second CU at
a time,

- 36 -

where a second CU is always associated with a third CU at a time, and

where there exist second CUs of at least a first and second type and/or third CUs of at least a first and

5 second type that require different choices of at least one parameter for use in the operation of said protocol,

characterised in that

10 in the case that it is possible that an association of said first CU with a second CU that is associated with a third CU of a first type may be changed to an association of said first CU with a second CU that is associated with a third CU of a second type,

15 said protocol entities of said first CU and said protocol entities of said third CU of the first type perform the step of exchanging at least one negotiation message containing a value for said parameter prior to said change of associations.

20

25

30

35

- 37 -

SC/cw 030233WO
March 26, 2003

ABSTRACT

5

The invention relates to a method and a computer program product for negotiation of a parameter for a protocol that controls data transmission between first Communication Units (CUs) and third CUs via second CUs.

10 An improved protocol parameter adaptation for certain non-transparent data call handovers is achieved by proposing that when an existing association of said first CU with a former second CU is changed to an association of said first CU with a new second CU, protocol entities
15 of the first CU and protocol entities of the third CU associated with the new second CU exchange at least one negotiation message containing a value for said parameter. The invention further relates to a system for data transmission.

20

For publication: Fig. 2.

1/5




Fig.1

2/5




Fig.2

3/5




Fig.3

4/5




Fig.4

5/5




Fig.5